TUMKUR DIVISION.

Dated 13th December 1911.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Tumkur Division, up to 15th January 1912, for restoring Ammasandra tank, Registered No. 236, Gubbi Taluk, Tumkur District. An approximate estimate of quantities is given below. These quantities are not guaranteed The work should be completed by the end of March 1913.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Tumkur between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees two hundred and fifty in cash or Government promissory notes, as earnest money, and be superscribed "Tender for restoring Ammasandra tank, Registered No. 236, Gubbi Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, Northern circle, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Detailed abstract estimate of Restoring Ammasandra tank, Registered No. 236 of Gubbi Taluk.

Items of work	*Per*	*Quantity*
Bund—		
1 Earthwork	C. yd.	2,790
2 New stone work	"	910
3 Old stone work with new jelly	"	427
4 Gravel backing behind revetment	"	362
5 Turfing	S. yd.	5,278
6 Grade stones including zero stones, index stones and lead slabs including cutting figures and painting	No.	21
7 Register number stone including cutting figures and painting	"	1
8 B. M. stones do do	"	2
9 Gauge stone	"	1
Sluice—		
10 Repairs to existing sluices	L. S. Rs.	
Right waste weir—		
11 Earthwork excavating foundation for body wall, toe wall and slab bed apron and the earth used for ring bund and dismantling and removing old masonry work wherever necessary	L. S. Rs.	
12 Burnt brick in surki mortar	C. ft.	4353
13 Surki concrete	"	549
14 Rough stone in surki mortar	"	1097
15 Burnt or trap stone in surki mortar	"	900
16 Burnt stone slabs with one line dressing	S. ft.	1768
17 Surki plastering	Sqr.	14·30
18 Cement pointing	"	23·16
Constructing a lifting dam—		
19 Earthwork excavating and cutting and clearing rock for foundation	L. S. Rs.	
20 Burnt brick or stone in surki mortar	C. ft.	2,027
21 Burnt stone slabs, dressed	S. ft.	319
22 Cutting holes in slab for inserting planks	L. S. Rs.	
23 Teakwood plank shutter with channel iron in pier for shutter to work	"	
24 Surki plastering or cement pointing	Sqr.	14·06
25 Rough stone work	C. yd.	20
26 Channel excavation earthwork	"	818

K. PONNAPPA,
Executive Engineer.